

specifications drawn by J. C. Haskell and
 A. C. Gunn, associate Architects, for the sum
 of \$ 73489.00

I will add or deduct excavation at
 the rate of 25 cts. per cubic yard.

I will add or deduct concrete
foundations at the rate of 17 cts. per cubic foot.

I will add or deduct Rubble Masonry at
 the rate of 15 cts. per cubic foot.

I will add or deduct ashlar facings of
 Douglas or Jefferson County stone at the rate of
50 cts. per superficial foot.

I will add one foot to the exterior height
 of the basement story leaving floor of basement
 where it now is, adding twelve inches to ashlar
 facings, twelve inches to height of glass in
 windows, for the sum of \$ and properly
 adjust approaches to the added height.

I will make basement window sills into
 a full continuous course around the building and
 ten inches thick, with the same exposure above ground
 as now shown and add \$

I will add or deduct plastering at the
 rate of 25 cts. per square yard.

I will execute the plastering in any of
 the accepted cements as directed by the local
 architect, including fiber, hair and finish and
 will add or deduct cents per square yard,
 this to take the place of the lime mortar specified.

I will add or deduct brick work measured
 at the rate of twenty bricks to the cubic foot at
 \$ 12.00 per 1000 brick.

In case award is made to me I will
 deliver on the site, or wherever the local architect
 directs, all timber for finish floors from clear,
 heart, rift sawed, long leafed, hard pine of dimensions
 1x4 in the rough stacked with lath between all
 boards, housed and protected as directed, all
 within 90 days from date of award, and two
 months before use. I will place all this floor
 lumber in a good dry pile, and keep it there
 one month when it shall be milled and laid (not
 more than ninety days allowed on this proposal).