

Saturday, September 27, 1913.

The Board met in regular adjourned session with all members present.

The contract with Gracker Bros for the work on Bowman Bridge as shown on page 543, was signed and accepted as follows: Copy:

This agreement made and entered into this 27th day of September, 1913, by and between the Board of County Commissioners of Douglas County, Kansas, consisting of Gus Brune, J. C. Helton, and J. L. Hoover parties of the first part and Gracker Brothers of Lawrence, Kansas, parties of the second part;

Witnesseth, that the said parties of the second part, for the consideration hereinafter mentioned, covenant and agree to make, erect, build and finish in a good, substantial and workmanlike manner, and in conformity with the plans, drafts, specifications and explanations thereof, which are herewith annexed and made a part hereof, out of good and substantial materials and in a good and workmanlike manner a concrete culvert upon the county road between Lawrence, Kansas, and Eudora, Kansas, at that point on the southwest quarter of Section thirty-three (33), Township twelve (12), Range (20), where the bridge known as the Bowman bridge is now located; to be completed on or about the 25th day of November 1913.

It is further agreed by and between the parties of this contract-

1. That all necessary excavations shall be made by the parties of the second part and that the cost of the excavation shall be included in the sum bid for the complete work.

2. That all material used in the work shall be subject to the approval of the Board of County Commissioners of Douglas County and the County Engineer of said County.

3. The cement shall be Kansas Portland Cement of a quality equal to "Tola" or "Sunflower" or "Bonner brands".

4. The sand shall be clean, sharp, Kaw River sand.

5. The broken stone shall be crushed limestone, the largest pieces of which shall not be more than two and one-half cubic inches ($2\frac{1}{2}$) in solid contents, the crusher dust and any dirt to be screened out of the crushed rock.

6. The concrete work shall be done in a neat and workmanlike manner and finished neat and true to lines. Vertical corners on the walls shall be rounded or chamfered. The concrete shall be mixed in the proportions called for on the plans.